


REG STATE PROJECT SHEET NO.

- I. Locations and height to be in accordance with the 'Manual on Uniform Traffic Control Devices for Streets and Highways' (MUTCD), latest edition.
- 2. Use wood battens bolted to post at vertical spacings not to exceed 30-inches.
- 3. Use double posts if W is over 3 feet.
- For sign punching details, see the blank standards in the "Standard Highway Signs" as specified in the MUTCD, latest edition.
- 5. For steel posts, provide a $\frac{1}{4}$ " x 6" soil plate. Use the same type of steel for the soil plate as for the post. Soil plate is not required for breakaway design.
- 6. For signs requiring posts sizes 6 x 6 and greater, signs are considered to be non-breakaway if multiple posts are required and posts cannot be spaced a minimum of 7 feet apart. Place non-breakaway signs outside the clearzone or shield with approved barrier. Do not place holes in posts of non-breakaway signs.



BREAKAWAY SUPPORT DETAIL

Post Size	Hole Diameter
4" x 4"	None Required
4" x 6"	<i>1</i> . 5″
6" x 6"	2"
6" x 8"	3"

U.S. DEPARTMENT OF TRANSPORTATION FEDERAL HIGHWAY ADMINISTRATION EASTERN FEDERAL LANDS HIGHWAY DIVISION

DETAIL

SIGN STRUCTURES

DETAIL APPROVED FOR USE --/---DETAIL REVISED: E633-I